

SURVEY & REMONUMENTATION

AUG 05 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>34W</u>	<u>B-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD THIS 2ND DAY OF AUGUST, A.D. 1994 AT 9:00 A.M. AI RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGE 483.

Dennis R. Destrampe
BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, Dennis R. Destrampe in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


Wood Post Original corner not found. Re-established 11/11/81, recorded in Liber 4, Page 50, Land Corner Recordation.
Hemlock 16 N52½E 68
Hemlock 12 N54W 29

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" re-rod as described in Liber 4, Page 50, Land Corner Recordation.

Witnesses found:

S face 22" Dead W. Pine N68E 25.83' PK & tag GCVN 27464
S face 20" Sugar Maple N79W 60.21' PK & tag GCVN 27464
Reference Monument USFS Brass Cap 1.00 East, stamped:



APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

T51N R34W
WC
SC 1/4 S31
1 Ft. West

KD
12-1-93

1962 RLS 12585

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 5/8" re-rod with 1"X36" pipe with 2½" brass cap 6" above ground.

Baraga Cty. Remonumentation brass cap stamped: SC

Witnesses:

S face Dead 22" W. Pine N68E 25.83' (Nail & tag "UPEA 18983" set)
W face 22" Sugar Maple S21E 24.94' (Nail & tag "UPEA 18983" set)
N face 12" Sugar Maple S51W 32.56' (Nail & tag "UPEA 18983" set)
S face 20" Sugar Maple N79W 60.21' (Nail & tag "UPEA 18983" set)

T51N R34W
1/4 S31
1994

Signed by *Dennis R. Destrampe*
Surveyor's Michigan License No. 18983

Date June 22, 1994