

SURVEY & REMONUMENTATION

AUG 05 1994

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Baraga	Located In:	Corner Code \neq	
(County)			
1. Public Land Survey	T <u>51N</u> R <u>34W</u>	<u>F-13</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

RECEIVED FOR RECORD THIS 2ND DAY OF AUGUST, A.D. 1994 AT 9:00 A.M. AI RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGE 482.

Nelda J. Schillard

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Dennis R. Destrampe, in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Post	Original corner found and perpetuated November 7, 1961;
Spruce 6 N43E 30	recorded April 13, 1964 in Book 2, Index Z-11, Page 22,
Do 8 N77W 25	of county records by Donald D. Lappala, R.L.S. 12585

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found corner as described in Book 2, Index Z-11, Page 22:

2" I.D. by 5' long, concrete filled, galvanized iron pipe, capped with a 3" circular brass tablet 1.7' above ground, which reads T.51N., R.34W.; $\frac{1}{4}$, S.C.; S-33; 1961

6" Black Ash N69°W 27.1 Feet (41 Links)

8" Black Ash N46°E 19.4 Feet (29 Links)

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner accepted as found. Rewitnessed:

Witnesses:	7" Ash N22W 36.63'	(Nail & tag "UPEA 18983" set)
	8" Ash N43E 19.44'	(Nail & tag "UPEA 18983" set)
	6" Ash S18E 22.11'	(Nail & tag "UPEA 18983" set)
	7" Ash N73W 27.03'	(Nail & tag "UPEA 18983" set)

Signed by *Dennis R. Destrampe* Date April 25, 1994
Surveyor's Michigan License No. 18983