

**SURVEY &
REMONUMENTATION**

MAY 17 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Baraga

(County)

Located in:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>51N</u> R <u>34W</u> | <u>G-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD THIS 30TH DAY
OF DECEMBER A. D. 1993 AT 10:30
A. M. AND RECORDED IN LIBER 4 OF
LAND CORNER RECORDATION ON PAGE
464.

Dennis R. Destrampe
BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Dennis R. Destrampe in a field survey on December 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													


A. Description of original monument and accessories and/or subsequent restoration:

Wood Post
Cedar 10 N36E 19
Do 7 N15W 23

Original corner not found. U.S.F.S. found scribed wood post in U.S.F.S. survey recorded in Volume 1 of Plats, January 7, 1964.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Wood post found by U.S.F.S. not found. Location reset from U.S.F.S. survey; corner fell in oxbow of Sturgeon River in about 2½' of water. A witness monument was set 15.00 feet east of corner location.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"X36" pipe with 2½" brass cap 0.9' above ground 15.00' east of corner location.
Baraga Cty. Remonumentation Brass cap stamped W.C.

T51N | R34W
S.33 | S.34

- | | | | |
|----------------------|------|--------|-------------------------------|
| Witnesses: 14" Cedar | N20W | 11.96' | (Nail & tag "UPEA 18983" set) |
| 8" Cedar | N12E | 23.40' | (Nail & tag "UPEA 18983" set) |
| 10" Cedar | S76E | 25.58' | (Nail & tag "UPEA 18983" set) |
| 9" Cedar | S32E | 22.83' | (Nail & tag "UPEA 18983" set) |

← 15'
1993

Signed by Dennis R. Destrampe Date December 28, 1993
Surveyor's Michigan License No. 18983