

SURVEY & REMONUMENTATION

AUG 05 1994

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Baraga **COMMISSION**
(County)

Located In: Corner Code ##

- | | | | | | |
|---------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey | T | 51N | R | 34W | L-13 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous
Property in Sec. | S | T | R | | |
| | S | T | R | | |

RECEIVED FOR RECORD THIS 2ND DAY
OF AUGUST, A.D. 1994 AT 9:00 A.M.
RECORDED IN LIBER 4 OF LAND CORNER
RECORDATION ON PAGE 481.

Della J. Robitard
BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Dennis R. Destrampe, in a field survey on December 17, 1993,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Wood Post Original corner not found. No record of subsequent restoration.
Cedar 8 N38E 30
Cedar 14 N45½W 18

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence found of original corner or subsequent restoration. Traverse was run from the southwest corner of Section 36 to the southeast corner of Section 36. The quarter corner was set at midpoint as per original notes.



APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-1-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"X36" pipe with 2½" brass cap 0.5' below grade, 3' south of the centerline of Manfeldt Road. Baraga Cty Remonumentation brass cap stamped:

S.C.
T51N R34W
1/4 36
S4
1993

- Witnesses:
Power Pole N18W 39.17' (Nail & tag "UPEA 18983" set)
5" Twin Apple N38E 83.84' (Nail & tag "UPEA 18983" set)
Power Pole S10W 27.58' (Nail & tag "UPEA 18983" set)
10" Apple S80W 106.10' (Nail & tag "UPEA 18983" set)

Signed by Dennis R. Destrampe Date June 7, 1994
Surveyor's Michigan License No. 18983