


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Baraga COUNTY
T 52N R 30W

DESCRIPTION OF CORNER 1/4 corner between Sections 34 and 35
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.
DATE MONUMENT PLACED AND WITNESSED June 24, 1970
WITNESSES TO CORNER..... Cedar 12 N75 $\frac{1}{2}$ °E (magnetic) 17.3 ft. "1/4S, NBT"



Cedar 13 S18°E (magnetic) 21.3 ft. "1/4S, NBT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found no evidence of original post or its accessories or of any replacement monuments or accessories.

Corner re-established on line between found section corners 40.068 ch. to north and to south. Corner position checks well with stream crossing to north and is on an abrupt change from upland to lowland course ENE, as recorded in original field notes. Found a location tag on a 12" cedar N78°W 38 links. (Note: there is an iron pipe purporting to be the S 1/16 corner between Sec. 34 and 35 S0°34'E 20.017 ch., not on official record. Set by unknown party).

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 28, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68