

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 52 N.R. 30 W


Bargua COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Secs. 32/33

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/14/65 with Magnuson

WITNESSES TO CORNER..... 16" Hemlock (1/4S NBT), S 67° W, 52 1/2 lks.



12" H. Maple (1/4S NBT), N 31° E, 35 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was set from Original BT down, rotted, upper face showing iron marks. (Hemlock: 8" N 47° W 24 lks.) other Hemlock stump to SE in proper bearing. Down blazed Hemlock in vicinity.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 9/10/1965
REGISTERED LAND SURVEYOR