

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY  
T 52 N R 30 W

DESCRIPTION OF CORNER North 1/16 corner between Sections 34 and 35

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED June 24, 1970

WITNESSES TO CORNER..... Hemlock 16 N84°E (mag.) 43.2 ft. "1/16S, BT"



Red Maple 5 N33°E (mag.) 45.9 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Not established in original survey.

No evidence that the corner had been established previously.

Found a location tag on a 4" maple S21°W .935 ch. from corner, but no monuments.

Corner established on line between section corner 20.034 ch. north and 1/4 corner 20.034 ch. south.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE September 28, 1971

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68