

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY
T 51-52N R 30W

DESCRIPTION OF CORNER 1/4 corner between Section 2 and 35

CORNER MONUMENT Witnessed pipe as found.

DATE MONUMENT PLACED AND WITNESSED June 29, 1970

WITNESSES TO CORNER..... Sugar Maple 11 N23°W (mag.) 12.6 ft. "1/4S, NBT"



Sugar Maple 16 S55°E (mag.) 22.0 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 1 1/2" I.D. x 30" iron pipe purporting to be the above coded corner. No evidence of original post or its accessories. Ford Motor Company location tag on nearby tree bears 1941 date. Monument is not on line between nor equidistant from section corners to E & W, being 39.823 ch. to corner to east and 40.209 ch. to corner to west. Eastbound on section line there is a 0°50'20" right deflection at the 1/4 corner.

Accepted monument as found.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE September 28, 1971

DISTRIBUTION:

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68