

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY
T 52 N R 30 W

DESCRIPTION OF CORNER 1/4 corner between Sections 26 and 35

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED June 22, 1970

WITNESSES TO CORNER..... Sugar Maple 10 N 8°E (mag.) 17.6 ft. "1/4S, NBT"



Sugar Maple 10 S71°E (mag.) 5.9 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found no evidence of original post or its accessories or of any re-
placement monuments or accessories. A 22" yellow birch bearing N3°W 54 links
from the re-established corner, alleged to be an original bearing tree, could
not be proved to be so by ring count into an old blaze. There are no other
identifying marks.

Corner re-established on line between section corner 40.61 ch. west and
section corner 40.61 ch. east.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 28, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68