


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Baraga COUNTY
T 52 N R 30 W

DESCRIPTION OF CORNER Center of NW $\frac{1}{4}$, Section 35
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED July 6, 1970
WITNESSES TO CORNER..... Sugar Maple 9 N14 $\frac{1}{2}$ ^oW (magnetic) 23.8 ft. "1/16S, BT"



Red Maple 6 N89^oW (magnetic) 34.4 ft. "1/16S, BT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Not established in original survey.
No evidence that the corner had been correctly established previously.
Found a forester's tree marked "Center of NW $\frac{1}{4}$ " S76^oW 1.55 ch. from corner.

Corner established at calculated distance south of W 1/16 corner between Sec. 26 & 35 and east of N 1/16 corner between Sec. 34 and 35, after first determining size and shape of exterior lines of Sec. 35 and establishing the center of the section.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

September 28, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68