

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY
T 52 N R 30 W

DESCRIPTION OF CORNER Center of Section 35

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 6, 1970

WITNESSES TO CORNER..... Cedar 9 S51°E (magnetic) 46.1 ft. "1/4S, BT"



Cedar 7 S22°W (magnetic) 35.1 ft. "1/4S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Not established in original survey.

Found blazed line intersection at corner, but no evidence that the corner had been precisely established previously.

Corner established at calculated intersection of quarter-lines, but was run in by transit line only on the calculated bearing and distance from the E $\frac{1}{4}$ corner of Sec. 35.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

September 28, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68