

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY
T 52 N R 30 W

DESCRIPTION OF CORNER Section Corner 25, 26, 35, and 36

CORNER MONUMENT Witnessed the pipe found in place

DATE MONUMENT PLACED AND WITNESSED June 24, 1970

WITNESSES TO CORNER..... Red Maple 11 S62°E (magnetic) 17.6 ft. "S25, NBT"



Cedar 7 N71°W (magnetic) 26.3 ft. "S26, NBT"

Hemlock 8 S 3°W (magnetic) 39.1 ft. "S35, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 1" I.D. iron pipe in place, also a very old, rotted squared cedar post lying on ground. Pipe possibly set by Ford Motor Company forestry personnel, because of Ford location tag on nearby tree dated 8/18/55. Also found a wood post bearing several names at the corner. Corner checks with stream crossings 6.00 ch. west and 2.50 ch. north and with other corners on perimeter of Section 35. No evidence of original post or its accessories.

Corner accepted and re-witnessed as found.

SURVEYOR'S SEAL

SIGNED

Arthur O. Eger
REGISTERED LAND SURVEYOR
Arthur O. Eger

DATE September 28, 1971

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68