


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Baraga COUNTY
T 52 N R 30 W

DESCRIPTION OF CORNER Section Corner 26, 27, 34, 35
CORNER MONUMENT Replaced the found iron pipe with a 1" I.D. x 36"
iron pipe with 4" aluminum cap.
DATE MONUMENT PLACED AND WITNESSED June 24, 1970
WITNESSES TO CORNER..... Red Maple 18 S30°E (mag.) 5.7 ft. "S35, NBT"



Red Maple 11 S11°W (mag.) 40.3 ft. "S34, NBT"
Sugar Maple 7 N35°E (mag.) 6.1 ft. "S26, NBT"
AND
Y. Birch 10 N38°W (mag.) 17.0 ft. "S27, NBT"

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 1 3/4" O.D. x 36" iron pipe in place, apparently long accepted and used as the corner by local land owners. The position checks well with river crossings to the south and east and with other corners around Sec. 35. Many old blazed trees in vicinity; blazed lines to E, W, and S intersect here. Ford Motor Company location tag bearing date 3/30/49 on tree to SE. Found no evidence of original post or its accessories.

Corner accepted as found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

September 28, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68