

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY
T 51-52N R 30W

DESCRIPTION OF CORNER Section Corner 1, 2, 35, and 36

CORNER MONUMENT Witnessed monument as found.

DATE MONUMENT PLACED AND WITNESSED June 29, 1970

WITNESSES TO CORNER..... Red Maple 12 S75°E (magnetic) 31.6 ft. "S1, NBT"



Sugar Maple 9 S77½°W (magnetic) 15.0 ft. "S2, NBT"

Sugar Maple 10 N38°E (magnetic) 20.9 ft. "S36, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 1/2" I.D. Iron pipe nested inside a 1-1/2" I.D. x 30" iron pipe in place. Possibly set by Ford Motor Co. forestry personnel sometime between 1949 and 1955. Found 3 stumps corresponding in species, bearing, and distance to the original bearing trees, no marks except for possible trace of face overgrowth and axe mark on stump to SE. Distances check to Huron River crossings to E and N. Many old blazes in vicinity.

Monument accepted as marking the original corner position. Distance to 1/4 corner to west is 39.82 ch., to 1/4 corner to north is 39.855 ch.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 28, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68