

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES


LAND CORNER RECORD

Baraga COUNTY
T 51-52N R 30W

DESCRIPTION OF CORNER Section Corner 2, 3, 34, and 35
CORNER MONUMENT Replaced the found iron pipe with a 1" I.D. x 36"
iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED June 24, 1970

WITNESSES TO CORNER..... Hemlock 14 N52°E (magnetic) 7.7 ft. "S2, NBT"



Hemlock 15 N65°W (magnetic) 23.1 ft. "S34, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 1-3/4" O.D. x 36" iron pipe in place, possibly set by Ford Motor Co. forestry personnel. Found Ford location tag on nearby tree bearing date 8/18/55. Old blazes on trees in corner vicinity. Found no evidence of original post or its accessories, but corner shows general agreement with other corners around Sec. 35.

Corner accepted as found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 28, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68