

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY
T 52N R 30W

DESCRIPTION OF CORNER 1/4 corner between Sections 35 and 36.

CORNER MONUMENT Witnessed pipe as found.

DATE MONUMENT PLACED AND WITNESSED June 29, 1970

WITNESSES TO CORNER..... Cedar 11 S13°W (magnetic) 14.6 ft. "1/4S, NBT"



Hemlock 11 N16°W (magnetic) 24.2 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a rusty 1" I.D. iron pipe with a pipe coupling screwed on top, purporting to be the corner coded herein. Also found 2 wood posts (one on ground) at pipe. Ford Motor Co. location tag bearing 1949 date is on a nearby tree, and nearby cruiser's tree shows 1955 dates. Corner not on line nor equidistant from section corners to N & S (40.065 ch. to N, 39.855 ch. to S, with 0°07'20" left deflection at 1/4 corner when going north). No evidence of original post or its accessories.

Accepted corner as found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 28, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68