

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

*PARAGIA*

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. <u>52</u> N. <u>30</u> R. <u>30</u> <u>W.</u>	<u>B 1</u>
2. PROPERTY CONTROLLING IN SECTION-- <u>6</u>	T. <u>52</u> N. <u>30</u> R. <u>30</u> <u>W.</u>	<u>2a</u>
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. .... N. .... R. ....	.....
4. LOT NO. ...., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were in a field survey on see below 19... established, re-established, monumented, re-monumented, recovered, restored as expressed below and in conformance with regulations and rules therefore as required in the corner notes of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 1 and 2 above were in a field survey on 19... found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or by a Decree of a court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner B1: Wood Post (Not found)
    - Sugar 16 S21W 28 " "
    - Maple 11 N11E 5 " "
  - No subsequent monuments found.
  - Corner 2a: Wood post (Not found)
    - Cedar 7 S71W 41 " "
    - W. Birch 10 N33W 6 " "
  - Found a squared wood post set by DNR foresters for an approximate M.C. S71½ E 73 links.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner B1: Established on 6/7/73 40.00 ch. E'ly of township corner on true section line between Sec. 6 & 31, as determined from relative positions of corners on the range line between Ranges 30 & 31 west and the original meanders of the north shore of Huron Bay in Sec. 6.
  - Corner 2a: This represents the Meander Corner between Sec. 6 & 31 on the north shore of Huron Bay, but is not intended to mark the original M.C. position. The monument was placed on the true section line as described for Corner B1, above, 58.25 ch. E'ly of the township corner. Not placed at record distance because of danger of the shoreline eroding and destroying the monument which marks the direction of the section line terminating at the water's edge.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.
  - Witnesses for Corner B1: Cedar 6 N73°E (mag.) 12.9 ft. "1/4S, NBT"
  - Cedar 15 N79°W (mag.) 11.5 ft. "1/4S, NBT"
  - Witnesses for Corner 2a: Cedar 16 N21°W (mag.) 35.1 ft. "MC, NBT"
  - Cedar 10 N67½°W (mag.) 67.1 ft. "MC, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_  
 FOR STATE AND UNITED STATES AGENCIES

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 APPROVED AND SIGNED BY *Arthur O. Enger* DATE **October 23, 1973**  
**Arthur O. Enger**  
 Michigan Department of Natural Resources