

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

ZARAGA

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 52 N. 30 R. 30 E. W.	A 2
2. PROPERTY CONTROLLING IN SECTION 6	T. 52 N. 30 R. 30 E. W.	10a
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19__ established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19__ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A2: Wood post (not found)

Cedar 10 N55W 4 " "
Hemlock 22 S78E 3 " "

Found a 4" x 4" x 6' squared cedar post set by DNR foresters for an approximate corner.

Corner 10a: Wood post (not found)

Hemlock 10 N69W 15 " "
W. Pine 18 N66E 21 " "

No replacement monuments found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A 2: Re-established on 6/6/73 on S'yly projection of true line between Sec. Corner 25, 30, 31 & 36, T53N, R30-31W and Sec. Cor. 1, 6, 31, & 36, T52-53N, R30-31W, at record distance of 40.00 ch. from the latter corner. Found this to be consistent with the original field notes.

Corner 10a: This is the Meander Corner between Sec. 1 & 6 on the north shore of Huron Bay. Re-established on 6/7/73 on S'yly extension of line described for Corner A2 above, at record distance from township corner. Position fits well with shoreline and with original meanders of the shore line in Sec. 6, T52N, R30W, Monument marks direction of section line, which terminates at the water's edge.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A2: 1" I.D. x 36" iron pipe with 4" aluminum cap

Red Maple 6 S80°E (mag.) 11.1 ft. "1/4S, NBT"

Red Maple 6 S28°W (mag.) 22.2 ft. "1/4S, NBT"

Corner 10a: 1" I.D. x 30" iron pipe with 4" aluminum cap, anchored in concrete.

Red Maple 9 N55°W (mag.) 60.5 ft. "MC, NBT"

Red Maple 5 N35°E (mag.) 87.8 ft. "MC, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 23, 1973

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581