

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 16 T 52N R 30W _____	1
	S 26 T 52N R 30W _____	PCC Sec. 26
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on PCC 04/18/2011 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(1-Sec. 16) West 1/16 corner between Sections 9-16. Not established in the original survey.

(PCC Sec. 26) Property Controlling Corner on the South 1/16 line of Section 26. The position was not established in the original survey. The position is on the East bank of the Big Huron River 461.15' east of 1/16 corner #10, Sec. 26 and 874.97' west of 1/16 corner #11, Sec. 26.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 16) Established the corner 20 chains (1320.00 ft.) west of monumented Quarter corner F5 and on the Section line between F5 and the recorded Witness Corner to the Meander Corner at Lake Superior, 828.63' west.

(PCC Sec. 26) The position was established on a straight line between monumented 1/16 corners #10 and #11, Section 26 and marks a point on the north line of the SW 1/4 of the SW 1/4 of the Section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 9" Hemlock N41E 18.5' mrkd "1/16S BT"
 7" Hemlock S85E 14.3' do
 15" Hemlock S23W 5.6' do
 9" Hemlock N86W 5.2' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

(PCC) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 7" Sugar N57E 28.55' mrkd "POL BT"
 6" Spruce S42E 13.3' do
 8" Maple S64W 22.25' do
 6" Sugar N56W 14.35' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/18/2011

For the Michigan Department of Natural Resources, Office of Land and Facilities

