

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 32 T 52N R 30W	14
	S 32 T 52N R 30W	9
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 9 06/24/13
14 06/19/13 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(14-Sec. 32) South 1/16 corner between Sections 32 and 33. Not previously monumented.

(9-Sec. 32) East 1/16 corner, Section 32. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14-Sec. 32) Established the position for the corner midway and on the Section line between Quarter corner 1316.39' north and Section corner 1316.39' south.

(9-Sec. 32) Established the position for the corner on a straight line between Center of Section 32 1334.06' west and Quarter corner 1334.06' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
9" Spruce N05°E 49.6' mrkd "1/16S BT"
4" Spruce N22°E 26.8' do
8" Spruce S04°W 54.3' do
9" Maple N51°W 57.5' do
Set sq'd spruce post adjacent.
E= 7913904.497 N= 230906.169

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
11" Maple N75°E 10.2' mrkd "1/16S BT"
4" Maple S69°E 8.05' do
8" Maple N68°W 21.3' do
9" Maple N36°W 18.2' do
Set sq'd cedar post adjacent.
E= 7913511.199 N= 231313.992

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).
Coord. Ref.=NGS PID D08499: N= 221257.624 m. E= 7884435.168 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 08/15/2013

For the Michigan Department of Natural Resources, Forest Resources Division

