

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>30W</u>	<u>113</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 01 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (113) Corner common to Sections 34-35 T52N-R30W and 2-3 T51N-R30W. Corner established in 1845 by Wm. A. Burt. Additional BTs made by Wm. Ives during his subdivision of T51N-R30W in 1846: South corrected Sugar 11 S65E 14, Hemlock 9 S45W 30. Notes of Norman T. Thompson, Ford Motor Co. surveyor dated 3 Dec. 1941 state: Felix and Goddard set post at cor 2-3-34-35. B.T. Reading Hem stub S58W 18'8". Remonumented in 1970 and recorded in 1971 by A.O. Enger who found 1-3/4" O.D. x 36" iron pipe with Ford location tag nearby dated 8/18/55. Enger found no original evidence. Enger placed 1"IDx36" iron pipe with 4" aluminum cap at location of found IP and made NBTs: Hemlock 14 N52E 7.7', Hemlock 15 N65W 23.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (113) The 1970 monument was found in place but bent over by logging operations. Removed the monument and placed a new one in the hole left by it and at record bearing and distance from the remaining 1970 NBT Hemlock N65W 23.1', now a 4' stub with blaze and notch plain. The other Hemlock NBT has been windthrown.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (113) Set 1"IDx32" iron pipe with 4" alum. MDNR cap. Blazed and scribed:
 20" Hemlock N09W 34.1' "S34 NBT"
 5" Y. Birch N57E 29.7' "S35 NBT"
 7" Y. Birch S28E 12.8' "S2 NBT"
 16" Hemlock S24W 28.3' "S3 NBT"
 Sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/01

For the Michigan Department of Natural Resources - Forest Management Division