

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T 52N R 30W	A12	
	T 52N R 30W	A11	
2. Property Controlling in Section	T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

A11 Jun 23 2005  
 A12 Jun 16 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (A12) Quarter corner common to Section 31 T52N-R30W and Section 36 T52N-R31W. 1845 - Established by Wm. A. Burt, Deputy Surveyor. North on East side of Sec. 36 T52N-R31W ...40.00 Set qr. Section post. Y.Birch 10 S40E 310, Maple 12 N6W 11. ...80.00 Set corner post of Secs. 25&36.
- (A11) Corner common to Sections 30-31 T52N-R30W and Sections 25-36 T52N-R31W. 1845 - Established by Wm.A.Burt, Deputy Surveyor: North on east side of Sec. 36 T52N-R31W ...80.00 Set corner post of Sections 25&36. Sugar 12 N70E 15 links, Y.Birch 16 S86W 33 links. Circa 1929 - Michigan Dept. of State Highway alignment notes for STL 35-10 (now Skanee Rd.) show: Sta. 891+34.8 P.I. #18 Cor. post com. to Sec 25&36 T52N-R31W and Sec. 30&31 T52N-R30W. No mention of monument type. Witness to corner is spike in 16" Hemlock S41 deg.15'E 72.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (A12) The original post and accessories were not recovered. Reestablished the corner midway and on line between monumented corners A11 and A13 2643.72' north and south.
- (A11) The original post and accessories were not recovered. Found no monumentation at the corner position. The MDSH witness was not recovered. Reestablished the corner in the center line of the pavement of Skanee Rd. and by proportionate measurement to the MDSH record between corner K11 T52N-R31W to the west (MDSH station 838+42.6) and the center of a N-S railroad (now a grade with no rails) to the east (MDSH station 972+12.5). The position thus established is 5396.72' west of C11 as reestablished by the undersigned (5356.6' GLO), 5293.09' east of monumented K11 T52N-R31W (5280' GLO), 5287.44' north of monumented A13 (5280' GLO), and 5272' south of monumented A9 (5280' GLO).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |  |
|--|--|
| (A12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:<br>16" Hemlock N61E 11.2' mrkd "1/4S NBT"<br>9" Hemlock S48E 2.5' do<br>9" Ash S34W 8.6' do<br>8" Y.Birch N27W 9.1' do<br>Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (A11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap 6" below asphalt surface of Skanee Rd. Set measuring nails in:<br>6" Maple N31E 54.8' mrkd "S30 NBT"<br>10" W.Ash S60E 78.2' "S31 NBT"<br>6" Maple S46W 52.5' "S36 NBT"<br>Power pole H249 N56W 63.5'<br>Bearings are magnetic. Distances are to nail with tag. |
|--|--|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 11/22/05

For the Michigan Department of Natural Resources, Office of Land and Facilities