

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

BARAGA

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER

1. PUBLIC LAND SURVEY T. 52 N. R. 31 W. L 1 & M 1

2. PROPERTY CONTROLLING IN SECTION T. N. S. R. E. W.

3. MISCELLANEOUS PROPERTY IN SECTION T. N. S. R. E. W.

4. LOT NO. RECORDED PLAT

5. PRIVATE CLAIMS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram) were in a field survey on see below 19 , established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were in a field survey on 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or by a Decree of a court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner L 1: Wood post (not found)
Cedar 9 S20W 20 " "
Cedar 11 N61E 16 " "

No subsequent monuments found.

Corner M 1: Wood post (not found)
Y. Birch 15 S34W 42 " "
Hemlock 15 N34E 13 " "

Found a forester's approximate post S1°E 81½ links, and a 26" hemlock with old blazes on 4 sides S58°W 22 links.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner L 1: Re-established 6/6/73 on line between sec. corners 40.00 ch. to E and to W.

Corner M 1: As the section lines going to E and S from this township corner are fractional, re-established this corner at record distance of 80.00 ch. S of an original corner to N and 80.00 ch. E of an original corner to W. Found this position to agree quite closely with the fractional distances to the shoreline of L. Superior to S and to E. Found a 28" hemlock S29°E 50 lks. which had an old blaze facing west, upon which were timber scribe "doodles". Although this appears as though it might have been made at the time of the original survey, it apparently has no relationship to the corner, as far as I can tell. **Corner re-established on 9/27/72.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner L 1: Red maple 6 S40°E (mag.) 6.0 ft. "1/4S, NBT"
W. birch 6 N72½°E (mag.) 17.4 ft. "1/4S, NBT"

Witnesses for Corner M 1: Hemlock 17 N27°W (mag.) 29.9 ft. "S36, NBT"
Hemlock 20 N65°E (mag.) 42.0 ft. "S31, NBT"
Hemlock 13 S61°E (mag.) 22.7 ft. "S 6, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES: _____

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY *Arthur O. Enger*
MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**

October 23, 1973

