

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Baraga _____	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>11</u> T <u>52N</u> R <u>31W</u>	<u>6</u>
	S <u>11</u> T <u>52N</u> R <u>31W</u>	<u>2</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Oct 30 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3										●			
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (6-Sec. 11) Northeast 1/16 corner. Not established in the original survey.  
 (2-Sec. 11) East 1/16 corner between Sections 2 and 11. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.**

(6-Sec. 11) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.  
 (2-Sec. 11) Established midway and on a line of mean true bearing between Quarter corner 1319.77' west and Section corner 1319.77' east.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.**

(6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:	(2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:
7" Sugar N16E 11.4' "1/16S BT"	7" Y.Birch N64E 26.1' "1/16S BT"
6" Y.Birch S81E 30.7' do	6" Y.Birch S37E 6.0' do
7" Y.Birch S50W 15.5' do	6" Y.Birch N81W 24.3' do
6" Y.Birch N42W 7.6' do	12" Maple N06W 41.8' do
Squared a 7" Y.Birch S62W 4.6' to center. Bearings are magnetic. Distances are to notch in lower blaze.	Set squared spruce post adjacent. Bearings are magnetic. Distances to notch in lower blaze.



Signed by Stephan J. Szyszkoski Date 3/19/02  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Office of Property Management