

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Baraga</u>	Located In:	Corner Code #	
<small>(County)</small>			
<b>1. Public Land Survey</b>	T <u>52N</u> R <u>31W</u>	<u>K3</u>	
	T <u>52N</u> R <u>31W</u>	<u>J4</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
<b>2. Property Controlling in Section</b>	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
<b>3. Miscellaneous Property in Sec.</b>	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Nov 29 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3										●		
4	7	8	9	10					●		12	
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


**A. Description of original monument and accessories and/or subsequent restoration:**  
 (K3) Corner common to Sections 1-2-11-12. Established in 1846 by Wm. Ives: South between Sections 1 & 2...80.00 set post corners of Secs. 1-2-11-12. Sugar 10 N70E 20, Sugar 10 S78W 11. 1998 - Corner described on a 2 Jun 1998 survey by R.W.Crampton, PS (Drawing L-3-1740): NE cor. Sec. 11, 6" Y.Birch tree (fnd). Witnessed with a survey tag nailed to: 6" Maple N11E 15.20', 8" Y.Birch N89E 26.65', 10" Y.Birch S20W 27.95', 11" Maple N71W 51.70'.  
 (J4) Center of Section 11. Not established in the original survey. Monumented in 1998 by R.W. Crampton PS 2647.06' south of J3 on the N-S 1/4 line of Section 11, it being parallel to the East line of Section 11. Survey dated 2 Jun 1998, drawing no. L-3-1740.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(K3) Original post and accessories were not recovered. Found the 6" Y.Birch tree, squared, noted in the 1998 record and a 3/4" ID I.pipe with plastic cap #24591 1.0' southerly as a witness. The witnesses on the 1998 survey were found at record bearing and distance from the tree. Distances to corners N-E-W check well with the original record. I accept the tree as the best available evidence of the position of the original corner. I cut the tree at 7' a.g. to facilitate GPS observations. Distances to adjacent corners were measured as follows: K1-5273.10, L3-2648.10, J3-2639.55, and 2603.42' south to an Iron Pipe MC set by Mr. Crampton.  
 (J4) Recovered the 1998 monument of record N46E 27.7' from the intended 1998 position and disturbed by a windthrown uprooted tree. Reestablished the corner according to the 1998 method 2647.06' south of the Quarter corner and on a line parallel with the monumented East line of Section 11.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(K3) Fd. Squared 6" Y.Birch tree. Cut at 7' a.g. Found these witnesses (nail with brass washer in tree): 7" Sugar N08E 15.2' 8" Y.Birch N88E 26.7' 9" Y.Birch S19W 27.9' cut at 4' a.g. 10" Maple N74W 51.7' Found a 3/4" ID I.pipe with cap #24591 South 1.0' Bearings are magnetic.	(J4) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 9" dbl Hemlock N20E 51.7' "C1/4 BT" 8" Maple N48E 37.4' do 10" Maple S69E 29.0' do 7" dbl Sugar S28E 37.3' do Squared sugar post adjacent. A 10' high N-S fence is 95' westerly. Bearings are magnetic. Distances are to notch in lower blaze.
--	---



Signed by Stephan J. Szyszkoski Date 3/19/02  
 Surveyor's Michigan License No. 33986