

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

BARAGA COUNTY

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>52</u> <sup>N.</sup> <del>XX</del> , R. <u>33</u> <sup>XX</sup> <del>W.</del>	<u>G3, G4</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____, S. _____, R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____, S. _____, R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 6, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner G3:** Found two very old post and stumps of original B.T.'s. Tamarack 6" N63W 5 links and Tamarack 6" S49E 22 links.
- Corner G4:** Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner G3:** Restored from BT stumps.
- Corner G4:** Restored midway and on line between corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner G3:** Set 1" I.D.x32" iron pipe with 4" alum. cap.  
 9" Tamarack N16W 16.0 ft. S4,NBT  
 8" Spruce N47E 19.5 ft. S3,NBT  
 6" Cedar S46E 14.5 ft. S10,NBT
- Corner G4:** Drove 1" steel drift pin into blacktop county road.  
 10" Yellow Birch S33E 46.8 ft. 1/2S,NBT  
 Nail and DNR tag in: P. Pole N79E 153.80 ft.  
 P. Pole N75W 156.75 ft.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)  
 FOR STATE AND UNITED STATES AGENCIES.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-26-82  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
**Keith L. Sackett**  
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

