

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

BARAGA COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>52</u> ^{N.} XX , R. <u>33</u> ^{XX} W.	G2
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	T. <u>52</u> ^{N.} X , R. <u>33</u> ^X W.	14
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, R. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 7, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
Corner G2: Original monument and accessories not found.
Corner 14: Not set on original survey nor subsequently apparently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner G2: Restored by single proportion between corners north and south. Corner falls in deep east-west drain ditch.
Corner 14: Established midway and on line between corners north and south.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner G2: Set 1" I.D.x32" iron pipe 18.10 ft. south of corner, 225 ft. west of center line railroad tracks. Corner falls in deep drainage ditch.
Corner 14: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 5" Tamarack N70E 31.5 ft. 1/16S,BT
 6" Tamarack N13W 42.2 ft. 1/16S,BT
 10" Tamarack S15W 8.3 ft. 1/16S,BT


SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-26-82

CHIEF OF SURVEY PARTY

MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

