

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>52</u> N. X. R. <u>33</u> X. W.	<u>A-2, A-1</u>
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A-2: Original monument and accessories not found. Found 1" steel axle shaft and numerous blazes.

Corner A-1: Original monument and accessories not found. Found numerous blazes in area.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A-2: Reestablished 7-20-77 at axle shaft. Fits good with river south and corners north. Numerous blazes in area.

Corner A-1: Re-established 7-18-77 by double proportion. Good north-south blazed line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A-2: <sup>I.D.</sup> 1" x unknown length steel axle shaft.

20" Sugar N15°W 2.4' ¼S NBT  
 16" Sugar S50°E 12.6' ¼S NBT  
 9" Sugar N58°E 22.5' ¼S NBT

Corner A-1: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

6" Sugar N83°E 13.8' S31 NBT  
 7" Maple S49°W 8.5' S 1 NBT  
 8" Sugar N69°W 12.0' S36 NBT  
 Sq. 6" Sugar N35°E 3.4'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE August 3, 1977

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
**Keith L. Sackett**  
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

