

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>52</u> N. <u>33</u> E. <u>W.</u>	<u>G-7, G-5</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 13, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G-7: Original monument and accessories not found. Found old scribed post in line with fences north, east and west and roads south.

Corner G-5: Found original bearing tree - Cedar 12" N32°W 30 links.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G-7: Re-established at old post location.

Corner G-5: Re-established from original cedar which is now 17" Cedar N32°W 19.8'. Scribed T52N - R33W - S9 BT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G-7: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

4" Maple S66°E 30.7' S22 NBT
13" Maple N1°E 22.5 S15 NBT

Corner G-5: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

5" Cedar S63°W 7.5' S16 NBT
5" Cedar N83°E 15.8' S10 NBT
17" Cedar N32°W 19.8' S9 BT
T52N-R34W

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE August 3, 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

