

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 52 N. R. 33 E.	E-4
2. PROPERTY CONTROLLING IN SECTION	5 T. 52 N. R. 33 E.	16
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner E-4: Original monument and accessories not found.
- Corner 16: Not set on original survey. Found old fence corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner E-4: Re-established 5/5/77 at intersection of N-S ditch and E-W road from information in Liber 32, Page 462 of Deeds, and Liber 32, Page 460 of Deeds dated 6/10/12.
- Corner 16: Established by 5/20/77 at fence corner which is on line between section corner east and quarter corner west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner E-4: Set 5/8" x 12" rerod 10' south of painted center line.  
Nail in power pole S55°W 90.6'  
Nail in power pole S61°E 207.71'  
SW corner of milkhouse N71°E 194.86'
- Corner 16: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.  
No available witnesses. Corner falls in marshy field.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE August 3, 1977  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett  
Michigan Dept. of Natural Resources  
19006

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

