

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF:-	LOCATED IN-	CORNER CODE NUMBER
LAND SURVEY	52 N. R. 33 W.	A-7, A-9
LOCALITY CONTROL NO. IN SECTION	N. S., R. W.	
NEARBY LOCALITY IN SECTION	N. S., R. W.	
RECORDED PLAT		
PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 1977 established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3-4 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or by a decree of a Court of law:

Description of original monument and accessories and/or subsequent restoration:

- CORNER A-7: Original monument and accessories not found. Found 1½" I.D. x unknown length iron pipe buried in old logging road. Fits good with corners north and south.
- CORNER A-9: Original monument and accessories not found. Found 1¼" I.D. x unknown length iron pipe 1' above ground in line with roads north, south and west. Old blazed line east.

Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- CORNER A-7: Re-established 4-18-77 at pipe.
- CORNER A-9: Re-established 4-22-77 at pipe.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- CORNER A-7: 1½" I.D. x unknown length iron pipe buried in old logging road.
 - 9" Sugar S58°W 18.4' S24, NBT
 - 12" Sugar N69°W 19.2' S13, NBT
 - 16" Maple N80°E 16.2' S18, NBT
- CORNER A-9: 1¼" I.D. x unknown length iron pipe one foot above-ground.
 - 10" Sugar S30°W 32.3' S25, NBT
 - 9" Sugar S82°E 24.2' S30, NBT
 - 7" Sugar N42°W 45.0' S24, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE August 3, 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

