

**SURVEY &  
REMONUMENTATION**

FEB 23 1998

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>A-2*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 30TH  
DAY OF DECEMBER A.D. 1997 AT  
10<sup>30</sup> A.M. AND RECORDED IN  
LIBER 4 OF LAND CORNER  
RECORDATION RECORDS ON PAGE  
774 775

*Relda Bishop*

BARAGA COUNTY REGISTER OF  
DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on 8 July, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-2; West One-quarter Corner Section 6, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2; West One-quarter Corner Section 6, T52N, R33W;

Found a 1 1/8" x 36" steel rod sharpened at one end projecting 10" above ground as recovered by Keith Sackett, P.S. in 1977. Replaced this monument with a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2; West One-quarter Corner Section 6, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location projecting 6" above ground.

i)	Set 7" spike	SE/side	8" Yellow Birch	N82°E	64.75'
ii)	Set 7" spike	SW/side	17" Sugar Maple	S51°E	13.47'
iii)	Set 7" spike	E/side	7" Sugar Maple	S24°W	49.60'
iv)	Set 7" spike	N/side	11" Sugar Maple	S78°W	5.70'
v)	Set 7" spike	S/side	10" Sugar Maple	N50°W	27.79'
vi)	Set 7" spike	S/side	20" Sugar Maple	N15°W	3.16'
			6' Steel fence post w/ yellow sign	North	1.5'

(i), (iii), (iv), and (v) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

(ii) and (vi) are Mr. Sackett's new bearing trees and are further described in Part A. These new bearing trees were also painted red.

\* This corner is also M-2 of T52N, R34W.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

10-9-97  
*[Signature]*



Signed by [Signature]

Date 19 Dec 1997

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

A-2; West One-quarter Corner Section 6, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Sugar            6            S23°E            26 lks.

and a

Lynn            14            N36°W            20 lks.

On 20 July 1977, Keith Sackett, P.S. #19006 recovered and accepted a "1 (in.) steel axle shaft". According to a Land Corner Recordation Certificate prepared by Mr. Sackett dated 3 August 1977 and recorded on 20 December 1977 in Volume 1 on page 489 of the Houghton County Land Corner Records, this monument was left in place and the following accessories were established:

20" Sugar            N15°W            2.4'

Presently alive and 20" in diameter but leaning heavily to the east and showing signs of decay. Both blazes are partially healed and scribing is visible.

Set 7" spike    S/side            Measured    N15°W            3.16'

16" Sugar            S50°E            12.6'

Presently alive and 17" in diameter having a healed upper blaze and a partially healed lower blaze with scribing visible.

Set 7" spike    SW/side            Measured    S51°E            13.47'

9" Sugar            N58E°            22.5'

Found dead and fallen.

SURVEY &  
REMONUMENTATION

FEB 23 1998

SECTION