

**SURVEY &
REMONUMENTATION**

FEB 23 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 52N R 33W</u>	<u>A-4*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 30TH
DAY OF DECEMBER A.D. 1997 AT
10:30 A.M. AND RECORDED IN
LIBER 4 OF LAND CORNER
RECORDATION RECORDS ON PAGE
778-779

Helda Bishop

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 11 November, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-4; West One-quarter Corner Section 7, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4; West One-quarter Corner Section 7, T52N, R33W;

Found a 1" diameter galvanized iron pipe with 4" aluminum cap as set by Keith Sackett, P.S. #19006 of the Michigan Department of Natural Resources. This monument was most likely set during the mid-1970's and bears approximately N10°30'W 3.3 feet from the single proportioned position. This corner falls in an abandoned north-south powerline corridor. Accepted Mr. Sackett's monument as a careful and faithful reestablishment of the position of the original corner. I did not remonument the corner, but stamped "PA 345 1997" to the cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4; West One-quarter Corner Section 7, T52N, R33W;

Found a 1" diameter galvanized iron pipe with 4" aluminum cap stamped as to location projecting 12" above ground.

i)	Set 7" spike	N/side	5" Hemlock	N79°E	55.02'
ii)	Set 7" spike	W/side	12" Yellow Birch	S32°E	65.31'
iii)	Set 7" spike	SE/side	7" Hemlock	S40°W	37.13'
iv)	Set 7" spike	N/side	9" Sugar Maple	S84°W	39.10'
v)	Set 7" spike	E/side	17" Red Maple	N12°W	66.54'
vi)	Set 7" spike	S/side	15" Sugar Maple	S53°W	24.58'
vii)	Set 7" spike	N/side	24" Twin Red Maple	N69°W	34.04'
			6' Steel fence post w/ yellow sign	East	1.5'

(i), (ii), (iii), (iv), and (v) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

(vi) and (vii) are presumably Mr. Sackett's new bearing trees having partially healed upper and lower blazes with scribing visible. Both blazes and a band around the tree at the upper blaze were painted red.

*This corner is also M-4 of T52N, R34W.

LIBER 4 PAGE 778

Signed by *Michael Mileski*

Date 19 Dec 1997

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4	●	7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

10-9-97
[Signature]



A. Description of original monument and accessories and/or subsequent restoration:

A-4; West One-quarter Corner Section 7, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Fir 12 N34°E 33 lks.

and a

Hemlock 14 N35°W 7 lks.

This corner was recovered and perpetuated by Peter A. Larsen in 1905. According to his cruiser's report dated August/September 1905, Mr. Larsen states that the fir U.S. bearing tree is "rotted" and that the hemlock U.S. bearing tree has "fallen down" and that he set a "cedar ¼ post" witnessed by a

Sugar 9 N37°W 13 lks.

and a

Birch 17 N08°E 27 lks.

SURVEY &
REMONUMENTATION

FEB 23 1998

SECTION