

**SURVEY &
REMONUMENTATION**

FEB 23 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in SECTION

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>A-5*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 30th
DAY OF DECEMBER A.D. 1997 AT
10:30 A.M. AND RECORDED IN
LIBER 4 OF LAND CORNER
RECORDATION RECORDS ON PAGE
780-781

Helda Bishop

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 20 November, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-5; Section Corner common to Sections 7 and 18, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5; Section Corner common to Sections 7 and 18, T52N, R33W;

Found a 1/2" x 18" iron rod set over a 1" x 24" galvanized iron pipe with a broken 4" aluminum cap at the intersection of the centerlines of Askel Road and Tower Road. Replaced found monuments with a 1" (I.D.) x 36" galvanized iron pipe with cap set inside of a monument box. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5; Section Corner common to Sections 7 and 18, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap inside a cast iron monument box.

Set 7" spike	NW/side	6" Cedar Fence Corner	N61°E	38.42'
Set 7" spike	SW/side	8" Aspen	S36°E	55.71'
Set 7" spike	NW/side	5" Red Maple	S30°W	139.82'
Set 7" spike	NW/side	6" White Birch	S47°W	108.29'
Set 7" spike	SE/side	Power Pole	S59°W	63.67'
Set 7" spike	NW/side	6" Red Maple	N29°W	156.18'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

*This corner is also M-5 of T52N, R34W.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5	●												
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

14-9-97
MS



LIBER 4 PAGE 780

Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 19 Dec 1997

A. Description of original monument and accessories and/or subsequent restoration:

A-5; Section Corner common to Sections 7 and 18, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Yellow Birch 14 N39°W 25 lks.

and a

Hemlock 30 N69°E 17 lks.

During the subdivision of T52N, R33W, by William Burt, D.S. in 1849, this corner was further witnessed by a

Hemlock 30 N65°E 17 lks.

and a

Sugar 7 S53°E 62 lks.

This corner was reestablished on 13 April 1973 by Arthur Enger, P.S. #13581 "at intersection of approximate construction centerlines of a N & S county road and a county road going W, which are presumed to be the section lines by common report". According to a Land Corner Recordation Certificate prepared by Mr. Enger dated 28 December 1973 and recorded in Liber 1 on page 123 of the Baraga County Land Corner Records, this corner was monumented with a 1" (I.D.) x 24" iron pipe with 4" aluminum cap witnessed by a

Nail in Power Pole S62°W (mag.) 66.19'

Stop Sign Post S16°E (mag.) 44.3'

Telephone Jct. Box N36°W (mag.) 94.0'

**SURVEY &
REMONUMENTATION**

FEB 23 1998

SECTION