

SURVEY & REMONUMENTATION

FEB 23 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

Baraga

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---------------------------|------|--|
| 1. Public Land Survey | T <u>52N</u> R <u>33W</u> | A-6* | |
| | T _____ R _____ | | |
| | T _____ R _____ | | |
| | T _____ R _____ | | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | | |
| | S _____ T _____ R _____ | | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | | |
| | S _____ T _____ R _____ | | |

RECEIVED FOR RECORD THIS 30TH DAY OF DECEMBER A.D. 1997 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGE 782

Relda Bishop

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 10 November, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-6; West One-quarter Corner Section 18, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Hemlock 6 N16°E 20 lks. and a Sugar 12 N69°W 40 lks.

No subsequent record evidence bearing upon the location of this corner was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6; West One-quarter Corner Section 18, T52N, R33W;

This corner was reestablished midway and on line between controlling government corners immediately to the north and south. The corner location falls 2.5 feet west of the physical centerline of a north-south, 20-foot wide, graded gravel road. This corner position is on the extension of the remains of a fence line to the west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6; West One-quarter Corner Section 18, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location 12" below the road surface.

- | | | | | |
|------|----------------------|------------------------------------|-------|---------|
| i) | Set 7" spike E/side | 6" Aspen | N40°E | 62.83' |
| ii) | Set 7" spike N/side | 4" Sugar Maple | N62°E | 101.28' |
| iii) | Set 7" spike SW/side | 5" Aspen | S35°E | 58.44' |
| iv) | Set 7" spike NE/side | Power Pole | N39°W | 59.71' |
| | | 6' Steel fence post w/ yellow sign | East | 33.0' |

(i), (ii), and (iii) are marked with upper and lower blazes. The lower blaze is marked "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

(iv) is marked with a vertical red stripe at shoulder height.

*This corner is also M-6 of T52N, R34W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

1079-97

2/3



LIBER 4 PAGE 782

Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 19 Dec 1997