

**SURVEY &
REMONUMENTATION**

FEB 23 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in SECTION

Baraga Located In: Corner Code #
(County)

1. Public Land Survey T 52N R 33W A-7*
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

RECEIVED FOR RECORD THIS 30TH DAY OF DECEMBER A.D. 1997 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGE 783-784

Helda Bishop

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 7 July, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-7; Section Corner common to Sections 18 and 19, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7; Section Corner common to Sections 18 and 19, T52N, R33W;

Found a 1 1/2" (I.D.) x 35" iron pipe 5 inches below the surface as recovered by Keith Sackett, PS in 1977. Replaced this monument with a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location. This corner falls on the physical centerline of a north-south, 10-foot wide, woods road. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7; Section Corner common to Sections 18 and 19, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location 8" below the surface.

- i) Set 7" spike NW/side 6" Sugar Maple N47°E 61.32'
- ii) Set 7" spike N/side 24" Twin Red Maple N80°E 16.73'
- iii) Set 7" spike N/side 8" Sugar Maple S63°E 33.63'
- iv) Set 7" spike N/side 10" Sugar Maple S60°W 18.78'
- v) Set 7" spike N/side 15" Sugar Maple N72°W 19.81'
- 6" Steel fence post w/ yellow sign West 20.3'

(i) and (iii) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

(ii), (iv), and (v) are Mr. Sackett's new bearing trees and are further described in Part A. These new bearing trees were also painted red.

*This corner is also M-7 of T52N, R34W.

LIBER 4 PAGE 783

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

11-19-97
[Signature]



Signed by [Signature]
Surveyor's Michigan License No. 39091

Date 19 Dec 1997

A. Description of original monument and accessories and/or subsequent restoration:

A-7; Section Corner common to Sections 18 and 19, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Sugar 12 N43°E 43 lks.

and a

Sugar 13 N21°W 42 lks.

During the subdivision of T52N, R33W, by William Burt, D.S. in 1849, this corner was further witnessed by a

Yellow Birch 15 S22°E 26 lks.

and a

Sugar 12 N42½°E 42 lks.

On 18 April 1977, Keith Sackett, P.S. #19006 recovered and accepted a "1½ (in.) I.D. x unknown length iron pipe buried in old logging road". According to a Land Corner Recordation Certificate prepared by Mr. Sackett dated 3 August 1977 and recorded on 20 December 1977 in Volume 1 on page 483 of the Houghton County Land Corner Records, this monument was left in place and the following accessories were established:

9" Sugar Maple S58°W 18.4'
Presently alive and 10" in diameter having partially healed upper and lower blazes with scribing visible.

Set 7" spike N/side Measured S60°W 18.78'

12" Sugar Maple N69°W 19.2'
Presently alive and 15" in diameter having partially healed upper and lower blazes with scribing visible.

Set 7" spike N/side Measured N72°W 19.81'

16" Maple N80°E 16.2'
Found an alive twin red maple 24" in diameter having partially healed upper and lower blazes with scribing visible.

Set 7" spike N/side Measured N80°E 16.73'

**SURVEY &
REMONUMENTATION**

FEB 23 1998

SECTION