

SURVEY & REMONUMENTATION

FEB 23 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>A-10*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 30TH DAY OF DECEMBER A.D. 1997 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGE 788

Helda Bekop

BARAGA COUNTY REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on 12 November, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-10; West One-quarter Corner Section 30, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Cedar	6	N47°E	21 lks.
and a			
Cedar	12	N78°W	15 lks.

No subsequent record evidence bearing upon the location of this corner was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10; West One-quarter Corner Section 30, T52N, R33W;

This corner was considered lost and reestablished midway and on line between controlling government corners immediately to the north and south. This corner is located in a transitional zone of high grass, black ash, red maple, and tag alder.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10; West One-quarter Corner Section 30, T52N, R33W;

Set a 1" (I.D.) x 72" galvanized iron pipe and cap stamped as to location projecting 12" above ground.

Set 7" spike	NW/side	10" Red Maple	N13°E	52.58'
Set 7" spike	N/side	10" Red Maple	N84°E	45.08'
Set 7" spike	W/side	12" Red Maple	S17°E	21.59'
		(in cluster of 5)		
Set 7" spike	E/side	9" Black Ash	South	61.10'
Set 7" spike	SW/side	6" Black Ash	N42°W	54.01'
Set 7" spike	NE/side	9" Red Maple	N35°W	22.36'
		6' Steel fence post w/ yellow sign	East	1.5'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

*This corner is also M-10 of T52N, R34W.

LIBER **4** PAGE **788**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County

10-9-97
JTT



Signed by *Michael Mileski*
 Surveyor's Michigan License No. 39091

Date 19 Dec 1997