

SURVEY & REMONUMENTATION

FEB 23 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>B-1*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 30TH DAY OF DECEMBER A.D. 1997 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGE 793
Helda Bishop
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 24 November, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1; North One-quarter Corner Section 6, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a Black Ash 8 N60°W 64 lks. and a Black Ash 16 N83°E 232 lks.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

10-4-97
[Signature]

The north line of section 6 was run by the Michigan Department of Natural Resources in 1977. The field notes of this survey do not mention an existing monument at the N¼ corner of section 6.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1; North One-quarter Corner Section 6, T52N, R33W;

This corner was considered lost and reestablished on line at the proportionate distance between the northwest corner of section 6 and the north one-quarter corner of section 5. The northwest corner of section 6 was reestablished by double proportionate measure in 1977 by Keith Sackett, P.S. of the Michigan Department of Natural Resources. The north one-quarter corner of section 5 is an original corner perpetuated by Keith Sackett, P.S. in 1977.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1; North One-quarter Corner Section 6, T52N, R33W;

Set a 1" (I.D.) x 72" galvanized iron pipe with cap stamped as to location projecting 6" above ground.

Set 7" spike	SE/side	8" Black Ash	N71°E	3.72'
Set 7" spike	NE/side	6" Black Ash	S38°E	25.75'
Set 7" spike	E/side	7" Black Ash	S12°W	16.71'
Set 7" spike	SE/side	8" Black Ash	S53°W	21.93'
Set 7" spike	S/side	6" Yellow Birch	N84°W	19.84'
Set 7" spike	W/side	6" Red Maple	N02°W	50.42'
		6' Steel fence post w/ yellow sign	South	1.5'



All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

LIBER 4 PAGE 793

*This corner is also B-13 of T53N, R33W.