

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	B-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 25th DAY  
FEBRUARY A.D. 2000 AT 10:30 A.M.  
AND RECORDED IN LIBER 5 OF LAND  
CORNER RECORDATION RECORDS ON  
PAGE 103 and 104.

*Fields Bishop*  
BARAGA COUNTY REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on July, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-3; One-quarter Corner common to Sections 6 and 7, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-3; One-quarter Corner common to Sections 6 and 7, T52N, R33W;

Mr. Enger's monument as described in Part A was apparently destroyed during road improvements. Reestablished this corner proportionately between the NW corner of section 7 and the NE corner of section 7 with due regard to Mr. Enger's noted deflection angle. This position falls in the physical centerline of an east-west, 20-foot wide, graded, gravel road. In the process of digging the hole for the new monument, a piece of 1" (I.D.) iron pipe approximately 4 inches long with a badly bent 1/2" x 12" iron rod typical of MDNR monuments was found 18 inches below the road surface. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-3; One-quarter Corner common to Sections 6 and 7, T52N, R33W;

Set a 1" (I.D.) X 36" galvanized iron pipe and cap 12 inches below the road surface.

Set 7" spike	NW/side	Power Pole	N37°E	27.03'
Set 7" spike	SE/side	Power Pole	N86°E	286.20'
Set 7" spike	E/side	Power Pole	South	290.19'
SW corner of concrete block wall	- House No. 228		N40°W	160.65'
6' Steel fence post w/ yellow sign			North	21.0'

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

12-16-99  
[Signature]



Signed by [Signature]  
Surveyor's Michigan License No. 39091

Date 27 Dec 1999

MAR 30 2000

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

B-3; One-quarter Corner common to Sections 6 and 7, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a sugar maple post witnessed by a

Sugar 14 N37°W 5 lks.

and a

Sugar 6 S34°E 20 lks.

In 1905, P.A. Larsen remonumented this corner with a "post. iron eye in top" from the northwest U.S. bearing tree and established the following accessory:

Sugar 12 S26°W 53 lks.

On 12 April 1973, Arthur Enger, PS #13581 of the Michigan Department of Natural Resources reestablished this corner "in construction centerline of a county road, taken to be the section line by common report, in line with a fence to N, which appears to be a property line of long standing. Proceeding E'ly on section line from NW cor. Sec. 7, there is at this corner a 0°31' left deflection angle to NE cor. Sec. 7". Mr. Enger monumented this position with a 1" (I.D.) x 24" iron pipe with 4" aluminum cap and noted the following accessories:

SE corner of telephone junction box N16°W (mag.) 22.4'  
Measured N18°W 21.8'

Nail head with 3/4" brass ref. marker tag on fence post S35°E (mag.) 31.35'

Refer to Land Corner Recordation Certificate filed by Mr. Enger and recorded on 1 August 1974 in Liber 1, pages 119-120, Baraga County Land Corner Records.