

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>B-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 25th DAY
FEBRUARY A.D. 2000 AT 10:30 A.M.
RECORDED IN LIBER 5 OF LAND CORNER
RECORDATION RECORDS ON PAGE 72.

Helda Bishop
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael Mileski, in a field survey on July, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	I
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5	●												
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-5; One-quarter Corner common to Sections 7 and 18, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a hemlock post witnessed by a Hemlock 15 N55°W 22 lks. and a Hemlock 10 S18°E 15lks.

In 1905, P.A. Larsen "set Hem Post 6" in hole of org. ¼ post". Mr. Larsen noted that the northwest U.S. bearing tree was down. He did not note any new accessories.

A sketch of section 7 prepared by Arthur Enger, P.S. of the Michigan Department of Natural Resources in 1972 indicates this corner as being monumented by a 1" dia. iron pin. Mr. Enger did not note any new accessories.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5; One-quarter Corner common to Sections 7 and 18, T52N, R33W;

Found a 1 ¼" x 36" iron rod projecting 15" above ground in a small rock collar in an east-west fence line. A fence also runs to the north. From this iron rod, a severely decayed hemlock stump having no marks bears S15°E a distance of 10.0 feet which is consistent with the original record. This monument bears N18°51'W a distance of 7.13 feet from the single proportioned position of the corner. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5; One-quarter Corner common to Sections 7 and 18, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap projecting 12 inches above ground.

Set 7" spike	SE/side	18" Red Maple	N27°E	27.14'
Set 7" spike	NE/side	9" Sugar Maple	S58°E	21.97'
Set 7" spike	W/side	8" Sugar Maple	S04°E	13.37'
Set 7" spike	S/side	11" Sugar Maple	S85°W	34.80'
Set 7" spike	NE/side	8" Sugar Maple	N43°W	18.19'
		6' Steel fence post w/ yellow sign	East	6.5'

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.



Signed by *Michael Mileski* LIBER 5 PAGE 72 Date 27 Dec 1999
Surveyor's Michigan License No. 39091

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

12-16-99