

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>B-7</u>	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

RECEIVED FOR RECORD THIS 25th DAY
FEBRUARY A.D. 2000 AT 10:30 A.M. A
RECORDED IN LIBER 5 OF LAND CORNER
RECORDATION RECORDS ON PAGE 74.

Helda Bishop

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael Mileski, in a field survey on July, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-7; One-quarter Corner common to Sections 18 and 19, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a hemlock post witnessed by a

- Hemlock 30 N68°W 26 lks.
- Yellow Birch 10 S30°E 13 lks.

No subsequent record evidence was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7; One-quarter Corner common to Sections 18 and 19, T52N, R33W;

This corner was remonumented at the base of an old fallen cedar post fence corner having fences to the east and south. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7; One-quarter Corner common to Sections 18 and 19, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe and cap projecting 4" above ground.

- Set 7" spike E/side 8" Sugar Maple N24°E 25.16'
- Set 7" spike SW/side 10" Sugar Maple S51°E 7.61'
- Set 7" spike SE/side 8" Sugar Maple S47°W 19.86'
- Set 7" spike S/side 15" Red Maple S81°W 52.62'
- 6" Steel fence post w/ yellow sign North 2.0'

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

12-16-99
[Signature]



Signed by [Signature]
Surveyor's Michigan License No. 39091

Date 27 Dec 1999