

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1-14

For corners in

Baraga
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|-------|
| 1. Public Land Survey | T <u>52N</u> R <u>33W</u> | B-9 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD THIS 14TH DAY OF
 JANUARY A. D. 1999 AT 10:30 A. M. A
 RECORDED IN LIBER 5 OF LAND CORNER
 RECORDATION RECORDS ON PAGE 16.

Relda Bishop
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on October, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-9; One-quarter Corner common to Sections 19 and 30, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a Cedar 8 N45°E 28 lks. and a Tamarack 10 S16°W 17lks.

No subsequent record evidence was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-9; One-quarter Corner common to Sections 19 and 30, T52N, R33W;

This corner was considered lost. The corner was reestablished on line at the proportionate distance between the NW corner of section 30 and the NE corner of section 30.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9; One-quarter Corner common to Sections 19 and 30, T52N, R33W;

Set a 1" (I.D.) X 96" galvanized iron pipe with cap stamped as to location projecting 20" above ground.

Set 7" spike	NW/side	8" Cedar	N35°E	21.00'
Set 7" spike	SE/side	12" Cedar	S49°W	23.10'
Set 7" spike	W/side	11" Cedar	S18°E	54.30'
		6' Steel fence post w/ yellow sign	North	1.0'

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County

12-17-98
[Signature]



Signed by *[Signature]*
 Surveyor's Michigan License No. 39091

Date 29 Dec 1998