

**SURVEY &
REMONUMENTATION**

FEB 23 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>R33W</u>	<u>B-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD THIS 31ST
DAY OF DECEMBER A. D. 1997 A
10:30 A.M. AND RECORDED IN
LIBER 4 OF LAND CORNER
RECORDATION RECORDS ON PAGE
804-805.

Relda Bishop

BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 19 November, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-13; South One-quarter Corner Section 31, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13; South One-quarter Corner Section 31, T52N, R33W;

Found a 2" x 30" iron pipe projecting 18" above ground perpetuated by persons unknown. This monument is close to the single proportioned position. Set a 1" (I.D.) x 36" galvanized iron pipe and cap along the north side of the found iron pipe. No evidence of Mr. Stockly's new bearing trees was found. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13; South One-quarter Corner Section 31, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location projecting 8" above ground.

Set 7" spike	NW/side	10" Red Maple	N22°E	34.85'
Set 7" spike	N/side	8" Red Maple	N56°E	33.13'
Set 7" spike	SW/side	10" Red Maple	S63°E	11.21'
Set 7" spike	E/side	6" Red Maple	S26°E	21.10'
		6' Steel fence post w/ yellow sign	North	1'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "SC NBT". Both blazes and a band around the tree at the upper blaze were painted red.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
16-9-97
[Signature]



LIBER 4 PAGE 804

Signed by *[Signature]*
Surveyor's Michigan License No. 39091

Date 23 Dec 1997

**SURVEY &
REMONUMENTATION**

FEB 23 1998

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

B-13; South One-quarter Corner Section 31, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Spruce 6 N02°E 22 lks.

and a

Maple 24 N35°W 11 lks.

This corner was reestablished on line at the proportionate distance between original government corners immediately to the east and west by William Stockly on 31 October 1907. Mr. Stockly monumented this corner with a 5" flattened cedar witnessed by a

Yellow Birch 8 S88°E 44 lks.

and a

Hemlock 8 S54°W 17 lks.

This information is from Mr. Stockly's field book No. 15, pages 1549 and 1550, on file at the Michigan Technological University archives.

1998