

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>C-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 25th DAY OF FEBRUARY A.D. 2000 AT 10:30 A.M. AM RECORDED IN LIBER 5 OF LAND CORNER RECORDATION RECORDS ON PAGE 73.

Helda Bishop

BARAGA COUNTY REGISTER OF DEED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael Mileski, in a field survey on July, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-2; One-quarter Corner common to Sections 5 and 6, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a hemlock post witnessed by a Yellow Birch 6 West 8 lks. and a Yellow Birch 8 S60°E 25 lks.

No evidence of subsequent restoration was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-2; One-quarter Corner common to Sections 5 and 6, T52N, R33W;

Reestablished corner midway and on line between the NE corner of section 6 and the SE corner of section 6. The original U.S. distance for this line is 80.00 chains. This position falls at the north edge of a logging trail bearing northeast and southwest.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-2; One-quarter Corner common to Sections 5 and 6, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap projecting six inches above ground.

Set 7" spike	E/side	6" Red Maple	N05°W	42.47'
Set 7" spike	SE/side	7" White Spruce	N45°E	6.14'
Set 7" spike	NE/side	13" Aspen	S27°E	33.98'
Set 7" spike	W/side	7" Red Maple	S10°W	26.74'
Set 7" spike	NE/side	7" Red Maple	N74°W	23.88'
		6' Steel fence post w/ yellow sign	South	1.0'

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

12-16-99
[Signature]



Signed by [Signature]

Date 27 Dec 1999

Surveyor's Michigan License No. 39091