

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>C-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 25th DAY  
FEBRUARY A.D. 2000 AT 10:30 A.M.  
AND RECORDED IN LIBER 5 OF LAND  
CORNER RECORDATION RECORDS ON  
PAGE 101 and 102.

*Hilda Bishop*

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on July, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-3; Section Corner common to Sections 5, 6, 7 and 8, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-3; Section Corner common to Sections 5, 6, 7 and 8, T52N, R33W;

Found 1/2" x 12" iron rod inside a 1" x 24" iron pipe badly bent two feet north of the physical centerline of an east-west, graded, gravel road. Although bent, the base of this monument appeared to be in its original position. This monument is 18 feet west of a fence to the north. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-3; Section Corner common to Sections 5, 6, 7 and 8, T52N, R33W;

Set a 1" (I.D.) X 36" galvanized iron pipe and cap 12" below the road surface.

Set 7" spike	SE/side	7" Aspen	N69°E	81.18'
Set 7" spike	SW/side	8" Balsam	N50°W	41.28'
Set 7" spike	E/side	16" Balsam	N01°W	34.26'
		6' Steel fence post w/ yellow sign	South	27.0'

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

12-16-99  
[Signature]

Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 39091

Date 27 Dec 1999

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3			●										
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



MAR 30 2000

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

C-3; Section Corner common to Sections 5, 6, 7 and 8, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a

Fir           ?       N52°W       27 lks.

and a

Black Ash    12       S55°E       15 lks.

On 12 April 1973, Arthur Enger, PS #13581 of the Michigan Department of Natural Resources reestablished this corner "in approx. centerline of E & W county road, taken to be section line by common report, midway between fence lines on either side. For departure set proportionately between ¼ corner 2635.3 ft. E (Record distance is 2634.0 ft.) and ¼ corner 2641.3 ft. W (record distance is 2640.00 ft.) From ¼ cor. to W, proceeding E'ly, there is a right deflection at this corner of 0°11'30" to ¼ cor. to E.". This position was monumented with a 1" (I.D.) x 24" iron pipe with 4" aluminum cap. The following accessories were noted:

Elm    9       N28°W (mag.)    32.3'  
Found 11" diameter elm stump five feet in height having no marks.  
Measured    N30°W           31.5' to center

Elm    6       N36°E (mag.)    34.8'  
Found 9" diameter elm stump five feet in height having no marks.  
Measured    N43°E           34.8' to center

Refer to Land Corner Recordation Certificate filed by Mr. Enger and recorded on 1 August 1974 in Liber 1, pages 119-120, Baraga County Land Corner Records.