

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>C-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 25th DAY (FEBRUARY A.D. 2000 AT 10:30 A.M. AM RECORDED IN LIBER 5 OF LAND CORNER RECORDATION RECORDS ON PAGE 71.

Richard Bishop
BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on July, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7	●	8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-4; One-quarter Corner common to Sections 7 and 8, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a sugar maple post witnessed by a Sugar 6 N79°E 30 lks. and a Sugar 6 S45°W 28 lks.

In 1905, P.A. Larsen remonumented this corner with a 3" diameter spruce post from the northeast U.S. bearing tree which he notes as "down". Mr. Larsen established the following new bearing tree:
Sugar 12 S45°E 50 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4; One-quarter Corner common to Sections 7 and 8, T52N, R33W;

Reestablished corner midway and on line between the NE corner of section 7 and the SE corner of section 7. This position falls 2 feet west of a 10-foot wide trail road that runs approximately north and south in an open hayfield.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4; One-quarter Corner common to Sections 7 and 8, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap six inches below ground. This corner is located in an open hayfield. There are no natural accessories available.

6' Steel fence post w/ yellow sign North 2.0'

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

12-16-99
[Signature]



Signed by [Signature]
Surveyor's Michigan License No. 39091

Date 27 Dec 1999