

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Baraga
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|-------|
| 1. Public Land Survey | T <u>52N</u> R <u>33W</u> | C-11 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD THIS 14TH DAY OF JANUARY A. D. 1999 AT 10:30 A. M. AND RECORDED IN LIBER 5 OF LAND CORNER RECORDATION RECORDS ON PAGES 17 AND 18.

Helda Bishop

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on July, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-11; Section Corner common to Sections 29, 30, 31 and 32, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11; Section Corner common to Sections 29, 30, 31 and 32, T52N, R33W;

Reestablished corner 30 links south of probable Stockly cedar witness post. The post was found fallen but the post bottom was clearly identifiable. This position falls in the centerline of an unimproved, 20 foot wide, east-west road (Sturgeon Road). Furthermore, this position bears N82°07'W a distance of 10.76 feet from the corner position as mathematically reconstructed from Mr. Stockly's survey of the east line of section 31. No other accessories were recovered for this corner. Accepted as the best available evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11; Section Corner common to Sections 29, 30, 31 and 32, T52N, R33W;

Set a 1"(I.D.) x 36" galvanized iron pipe with cap stamped as to location 12" below the road surface.

- | | | | | |
|--------------|---------|------------------------------------|-------|--------|
| Set 7" spike | N/side | 11" Aspen | N66°E | 38.19' |
| Set 7" spike | SW/side | Power Pole | S40°E | 35.68' |
| Set 7" spike | SW/side | 16" Red Maple | N50°W | 60.96' |
| Set 7" spike | W/side | 21" Red Maple | N16°W | 69.60' |
| | | 6' Steel fence post w/ yellow sign | South | 22.0' |



The power pole was marked with a vertical red paint stripe. The new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

Signed by _____

Date 28 Dec 1998

Surveyor's Michigan License No. 39091

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995

12-17-98
208

LIBER 5 PAGE 17

A. Description of original monument and accessories and/or subsequent restoration:

C-11; Section Corner common to Sections 29, 30, 31 and 32, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a white pine post witnessed by a

Tamarack 10 N67°W 23 lks.

and a

Spruce 10 S21°E 37 lks.

This corner was remonumented by William Stockly on 12 November 1907 from the stumps of both U.S. bearing trees. Mr. Stockly does not indicate the type of monument he set. He notes that the corner is located in a "wagon road" and that he set a 5" diameter cedar post 0.30 chains north of the corner and a 5" diameter cedar post 0.30 chains south of the corner. He also notes the following new bearing trees:

Spruce 5 S10°W 38 lks.

and a

Hemlock 5 S54°W 83 lks.

The field notes of a survey conducted on 5 September 1933 by persons unknown for Andrew and Joseph Lescelius of the north line of section 31 indicated "witness posts 30 links north and south of corner in road". No other accessories are noted.