

**SURVEY &  
REMONUMENTATION**

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

**COMMISSION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>C-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 23RD DAY OF OCTOBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 660-661.

*Helda McAntone*  
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on October, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-13; Standard Corner common to Sections 31 and 32, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13; Standard Corner common to Sections 31 and 32, T52N, R33W;

Found a 2 inch diameter iron pipe very firmly set and projecting 12 inches above the ground as described and accepted by the BLM in 1984. A thorough search for the remains of the U.S. bearing trees proved inconclusive. The similarity of this monument to those at the other corners listed in Part A and their harmonious relationship strongly implies their establishment by proper surveying techniques. This corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13; Standard Corner common to Sections 31 and 32, T52N, R33W;

Set a 1"(I.D.) x 36" galvanized iron pipe with a 2" aluminum cap appropriately stamped as to location at the north side of the found iron pipe. The following new bearing trees are in reference to the set iron pipe.

Set 7" spike	NW/side	10" Red Maple	N48°E	9.41'
Set 7" spike	NE/side	11" Red Maple	S53°E	25.66'
Set 7" spike	E/side	11" Red Maple	S18°E	29.65'
Set 7" spike	W/side	8" Sugar Maple	N16°W	43.98'
		C.C. Sec. 5 and 6	West	9.95'
		Location Post	North	1.0'



All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT SC". Both blazes as well as a band around the tree at the upper blaze are painted red.

Signed by *Michael Mileski*

Date 22 OCT 1996

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

C-13; Standard Corner common to Sections 31 and 32, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Hemlock      14      N25°E      33 lks.

and a

Yellow Birch   18      N60°W      10 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was found to be monumented with a 2 inch diameter iron pipe "from which the remains of the orig. bearing trees: A decayed hemlock stump, size indeterminate, bears N.25°E., 33 lks. dist., with no mks. visible. (and) A yellow birch stump hole, with the remains of charred wood, bears N. 60°W., 10 lks. dist.". Also during this survey the BLM recovered and accepted similar monuments at the N1/16 corner and the one-quarter corner common to sections 5 and 6, T51N, R33W, as well as the closing corner common to sections 5 and 6, T51N, R33W. At the latter two corners the BLM field notes state that the remains of the original bearing trees were recovered. The BLM did not remonument the corner nor did they note any accessories.

SURVEY &  
REMONUMENTATION

MAY 05 1997

COMMISSION