

**SURVEY & REMONUMENTATION**

**FEB 23 1998**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>D-1*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 30TH DAY OF DECEMBER A.D. 1997 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGE 795  
*Hilda Bishop*  
 BARAGA COUNTY REGISTER OF DEEDS

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1				●									
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Michael Mileski, in a field survey on 15 July, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1; North One-quarter Corner Section 5, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a Tamarack 7 N47°W 24 lks. and a Tamarack 6 N57°E 25 lks.

APPROVED LAND CORNER  
 P.A. 345 OF 1990  
 Baraga County  
10-4-97  
[Signature]

On 3 May 1977, Keith Sackett, P.S. #19006 of the Michigan Department of Natural Resources "Found possible BT stumps too far decayed for positive identification. Also found old post by P.A. Larsen set from original evidence." According to a Land Corner Recordation Certificate prepared by Mr. Sackett dated 3 August 1977 and recorded on 20 December 1977 in Volume 1 on page 481 of the Houghton County Land Corner Records, this monument was replaced with a 1" (I.D.) x 36" iron pipe with 4" aluminum cap. Mr. Sackett states that the corner falls in an open marsh and there are no available bearing trees.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1; North One-quarter Corner Section 5, T52N, R33W;

Found a 1" diameter iron pipe with a Michigan Department of Conservation 4" aluminum cap as set by Keith Sackett, P.S. in 1977. From this monument, two severely decayed tamarack stumps are located at the respective record U.S. bearing and distance. Left existing monument in place, adding "PA 345 1997" to the cap. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1; North One-quarter Corner Section 5, T52N, R33W;

Found a 1" (I.D.) iron pipe with a 4" aluminum cap stamped as to location projecting 6" above ground.

Set 6" spike	S/side	3" Tamarack	S51°E	51.31' (not scribed)
Set 6" spike	W/side	3" Tamarack	S33°W	40.50' (scribed "NRT")
	6' Steel fence post w/ yellow sign	North		1.5'

Both of the above new bearing trees are marked with upper and lower blazes. Both blazes and a band around the tree at the upper blaze were painted red.

\*This corner is also D-13 of T53N, R33W.

LIBER 4 PAGE 795



Signed by [Signature]  
 Surveyor's Michigan License No. 39091

Date 19 Dec 1997