

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	D-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 25th DAY
FEBRUARY A.D. 2000 AT 10:30 A.M.
AND RECORDED IN LIBER 5 OF LAND
CORNER RECORDATION RECORDS ON
PAGE 97 and 98.

Relda Bishop

BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael Mileski, in a field survey on July, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-3; One-quarter Corner common to Sections 5 and 8, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-3; One-quarter Corner common to Sections 5 and 8, T52N, R33W;

Found MDNR monument as described in Part A at approximate intersection of physical centerlines of roads to the south and west. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-3; One-quarter Corner common to Sections 5 and 8, T52N, R33W;

Found a 1" (I.D.) iron pipe with 4" aluminum cap as set by the Michigan Department of Natural Resources in 1973.

Set 7" spike	SW/side	18" Yellow Birch	S54°E	40.94'	(1973 MDNR NBT)
Set 7" spike	S/side	11" Black Ash	N86°E	32.98'	
Set 7" spike	W/side	7" Elm	N13°E	58.40'	
Set 7" spike	E/side	14" Elm	N36°W	36.21'	
		6' Steel fence post w/ yellow sign	North	2.0'	

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

12-16-99
Michael Mileski



Signed by _____

Date 27 Dec 1999

Surveyor's Michigan License No. 39091

MAR 30 2000

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

D-3; One-quarter Corner common to Sections 5 and 8, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a black ash post witnessed by a

Black Ash 8 N38°W 35 lks.

and a

Black Ash 6 S40°E 15 lks.

On 13 April 1973, Arthur Enger, PS #13581 and Keith Sackett, PS #19006 of the Michigan Department of Natural Resources reestablished this corner " 33 ft. W of, and in line with, fence corner and old fence to E, which places it nearly at the intersection of construction centerlines of county roads to S and to W. Distance W to twp. boundary is 8033.0 ft., original record distance is 8031.5 ft.". This position was monumented with a 1" (I.D.) x 36" iron pipe with 4" aluminum cap. The following accessories were noted:

Black Ash 10 S22°W (mag.) 109.2'

Found a 10" diameter severely decayed stump at this location.

Yellow Birch 9 S52°E (mag.) 40.9'

Presently alive and 18" in diameter having partially healed upper and lower blazes.

Set 7" spike SW/side Measured S54°E 40.94'

Refer to Land Corner Recordation Certificate filed by Mr. Enger and recorded on 1 August 1974 in Liber 1, pages 121-122, Baraga County Land Corner Records.